

---

# Electron Cooling Project: status and plans


Alexander Shemyakin

---

# Schematic Layout of the Recycler Electron Cooling

## Electron Cooling System Parameters

Parameter	Value	Units
<b>Electrostatic Accelerator</b>		
Terminal Voltage	4.3	MV
Electron Beam Current	0.5	A
Terminal Voltage Ripple	500	V (FWHM)
Cathode Radius	2.5	mm
Gun Solenoid Field	600	G
<b>Cooling Section</b>		
Length	20	m
Solenoid Field	150	G
Vacuum Pressure	0.1	nTorr
Electron Beam Radius	6	mm
Beam angular spread	$\leq 80$	$\mu\text{rad}$




# Stages of the project

---

- Proof- of- principle experiment at NEC 1995-1999
- Recirculation experiment at Wide Band 2001- 2002
- Full scale beam line at Wide Band 2003-2004
- Commissioning of ECOOL in Recycler 2005

# Recirculation experiment at WideBand



## HISTORY


- Feb 99: 5 MV Pelletron ordered.
- Dec 00: 5 MV without vacuum tubes.
- Mar 01: Tubes installed. Operations began.
- May 01: First beam of 30  $\mu$ A in the collector.
- Dec 01: 500 mA at 3.5 MV
- Apr 02: NEC replaced acceleration tubes
- Oct 02: 500 mA at 4.36 MeV
- Nov 02: Shut down to install the full beamline

# Recirculation experiment at WideBand


## Main results

- Stable operation at 0.5 A, 3.5 MeV (99% duty factor)
- 1.7 A of maximum current at 3.5 MeV (6 MW)
- 0.6 A of maximum current at 4.36 MeV
- Electronics survives sparks

An additional Pelletron section was ordered to be installed in MI 31.



# Full scale beam line at WideBand



## Current status

- cooling section magnetic fields measured
- beam line assembled and baked
- all diagnostics installed
- all BPMs are tested in pulsed mode
- $\mu\text{A}$  DC beam was transported up to the collector
- trouble spots were identified

The facility almost replicates the future MI 31 (shorter transfer lines and 9 instead 10 modules in the cooling section).

# Full scale beam line at WideBand

---



## Stages

Low-intensity DC beam  
in collector

Jul 03 ✓

Final measurements of magnetic  
field in cooling section

Aug 03

Stable 0.5 A at 3.5 MeV

Dec 03

Cold beam at 0.5 A, 3.5 MeV

Mar 04

# Cold beam in the cooling section

---

- The **beam center** moves along a straight line within  $70\ \mu\text{rad}$ . The straightness is controlled by 9 BPMs. The trajectory is adjusted by an entrance angle and by an average dipole field in each module of the cooling section.
- The boundary trajectory doesn't deviate from a straight line by more than  $80\ \mu\text{rad}$  in 90% of the cooling section length. The initial tuning of the **envelope** is done in a pulsed regime with a pencil-like beam. DC beam measurements are done with scrapers.



# ECOOL-related measurements in MI/RR tunnel

---

- Two **BPMs** have been installed in the Recycler at the future location of ECOOL. BPMs were connected to the final version of electronics capable of simultaneous measuring of electron and pbar beam's positions. Measurements with pbars shown resolution better than 50  $\mu\text{m}$ .
- A 2-m module of the cooling section has been installed in the Recycler at the future location of ECOOL above a MI quadrupole. **Magnetic fields** in the center of the module in the time of MI ramps are less than 2 mG, which satisfies ECOOL requirements.

# MI 31



MI 31 as of  
July 03

- Construction started in March 03 and is now 20% complete
- Completion is scheduled for March 04
- Additional Pelletron section arrives in January 04